

**"Notice Inviting Quotations/Bids"**

The Kangra Central Co-operative Bank Ltd., Head Office, Dharamshala intends to invite bids/quotations from interested vendors for installation of servo stabilizer in branches under the ~~area~~ jurisdiction area of Kangra Centerl Coop. Bank .

The cut-off date and time to receive the bids/quotations in physical form in the Drop-box placed at the suitable place of entry to the KCC Bank Technical Section at Head Office, Dharamshala is fixed as 10<sup>th</sup> Dec 2024 upto 1.00 PM sharp. Information regarding specified conditions to be quoted in the bid/quotation, cut off date & date of scrutiny, other related information is made available on page annexed below.

Contact number-

Sh. Malkiyat Singh – 01892-222269- Ext. 221 ,98050-75024

Sh. Vinod Kumar - 01892-222269- Ext. 200, 70184-45736



**Bids/Quotation required on Vendor/Company's Letter Head**

**Item: "Installation of Stabilizer"**

**SCHEDULE OF REQUIREMENT**

**Rate quoted**

SR. NO	Capacity of Servo Stabilizer	Rate quoted (In Rs including all taxes) (in figure and words) (Single phase & Three phase)			Specification		Installation Place
					Single phase	Three phase	
1	3KVA	90 <sup>+</sup>	110 <sup>+</sup>	160 <sup>+</sup>	Capacity:3KVA output voltage:230V input vottage :- 90 to 270V Mounting type:Floor Automaticv grade: Automatic Response time:10ms cooling:Air Cooled Time Delay:0 to 200 Sec	Capacity:3KVA output voltage:-440V input vottage 130 to 270V Mounting type:Floor Automaticv grade: Automatic Response time:10ms cooling:Air Cooled Time Delay:0 to 200 Sec Frequency:50Hz	area jurisdiction area of Kangra Centerl Coop. Bank .
	Single phase (Rs In Word)						
	Rs in figure						
	Three phase(Rs In Word)						
	Rs in figure						
2	5KVA	90 <sup>+</sup>	110 <sup>+</sup>	160 <sup>+</sup>	Capacity:5KVA output voltage:230V input vottage 90 to 270V Mounting type:Floor Automaticv grade: Automatic Response time:10ms cooling:Air Cooled Time Delay:0 to 200 Sec	Capacity:5KVA output voltage:440V input vottage:-130 to 270V Mounting type:Floor Automaticv grade: Automatic Response time:10ms cooling:Air Cooled Time Delay:0 to 200 Sec Frequency:50Hz	
	Single phase (Rs In Word)						
	(Rs in figure)						
	Three phase(Rs In Word)						
	(Rs in figure)						
3	6KVA	90 <sup>+</sup>	110 <sup>+</sup>	160 <sup>+</sup>	Capacity:6KVA output voltage:230V input vottage 90 to 270 Mounting type:Floor Automaticv grade: Automatic Response time:10ms cooling:Air Cooled Time Delay:0 to 200 Sec	Capacity:6KVA output voltage:440V input vottage 130 to 270 Mounting type:Floor Automaticv grade: Automatic Response time:10ms cooling:Air Cooled Time Delay:0 to 200 Sec	
	Single phase (Rs In Word)						
	(Rs in figure)						
	Three phase(Rs In Word)						
	(Rs in figure)						





	figure)					Frequency:50Hz
4	10KVA	90+	110+	160+	Capacity:10KVA output voltage:230V input vorage 90 to 270V Mounting type:Floor Automatic grade: Automatic Response time:10ms cooling:Air Cooled Time Delay:0 to 200 Sec	Capacity:10KVA output voltage:440V input vorage 130 to 270 Mounting type:Floor Automatic grade: Automatic Response time:10ms cooling:Air Cooled Time Delay:0 to 200 Sec Frequency:50Hz
	Single phase (Rs In Word)					
	(Rs in figure)					
	Three phase(Rs In Word)					
	(Rs in figure)					
5	15 KVA	90+	110+	160+	Capacity:15KVA output voltage:230V Mounting type:Floor Automatic grade: Automatic Response time:10ms cooling:Air Cooled Time Delay:0 to 200 Sec	Capacity:15KVA output voltage:440V Mounting type:Floor Automatic grade: Automatic Response time:10ms cooling:Air Cooled Time Delay:0 to 200 Sec Frequency:50Hz
	Single phase (Rs In Word)					
	(Rs in figure)					
	Three phase(Rs In Word)					
	(Rs in figure)					

**Terms & Conditions:**

1. Must have valid GST registration number.
2. Rates inclusive of material cost, transportation, erection, mounting ,GST and other taxes.
3. Rate should be quoted both in words and figures.
4. If there is difference between figures & words, words will be taken into consideration.
5. The Bank has solely right to increase or decrease the quantity of hoardings to be installed.
6. Earnest Money Deposit(s) of Rs 3,000/- in shape of Demand Draft/TDR. Details of EMD and the name of the agency should be clearly mentioned.
7. The EMD of the unsuccessful bidders will be returned back after placement of purchase order to the successful bidder and EMD of successful bidder will be returned after successful completion of the work.
8. The EMD will be forfeited if the tenderer withdraws its tender / furnish forged documents which is found during bid evaluation OR doesn't supply the items (in case of successful bidder) within the stipulated time period.



9. The purchaser shall be responsible only after delivery, installation and commissioning of the product by the supplier.
10. No advance payments will be made to the bidder/ vendor.
11. 100% of the bill value shall be paid to the bidder after the successful execution of the work.
12. Delivery: F.O.R.
13. Delivery period: within 15 days after receipt of purchase order.

**Schedule: Cut Off Date :10<sup>th</sup> Dec, 2024 (Tuesday)**

Vendors/Companies are invited to quote your rates preferably upto/on **:10<sup>th</sup> Dec, 2024 (Tuesday)** fixed as the date to receive the sealed bids/quotations in physical form in the Drop-box placed at the entry of KCC Bank Technical Section, Head Office, Dharamshala by 1.00 PM sharp and scrutiny of quotations will be held on the same day i.e:**:10<sup>th</sup> Dec, 2024 (Tuesday)** by 3.00 PM sharp.

